

Practical Test N208 Screener

	ACTIVITY GUIDELINES
	The learner must:-
Test sequence	 Complete all pre-start and running checks before any activity takes place The shutdown procedures must only be completed by the learner at the end of the test The screener must be set in the travel position with side chutes stowed and secured prior to the test starting All additional test requirements can be completed in any order
Operator safety & observations	 The screener must be sited correctly, level and stable with appropriate space for material discharge A risk assessment/method statement must be completed prior to screening The screener must be serviceable and meet the current legislation The learner must wear full PPE at all times Hand signals must be agreed with the loader learner before feeding commences
Set up in preparation for work	 Travel screener at least 30m over varying terrain (mobile only) Travel screener through a restriction Set screener in preparation for processing duties Receive a load
Process material	 Start the screener in the correct sequence Process material into at least 3 different sizes Carry out an emergency stop during the screening process
Shutdown procedures	The screener must be placed in a safe position with the key removed and handed to the instructor
Additional notes	 A verbal description to the instructor of the pre-start checks would be acceptable if the machine is hot The operator's manual must be available and accessible There must be suitable and sufficient material for feeding Appropriate method of feeding The material produced must be at least 75% of the discharge conveyer height If the screener test is used in combination with a crusher, the test would be complete when the screener produces 75% of its discharge conveyor height A screener that is not able to move and reposition for the test shall be classed as a static screener and the learner should be restricted to static screener use only The screener must be set to at least 75% of its full processing output capacity
Test timings	The full test must be completed within 1hr 15 min
Note	It is recommended that all learners completing basic training receive a minimum 7hr Health, Safety, Environment and Induction Training