

Test sequence	ACTIVITY GUIDELINES The learner must: <ul style="list-style-type: none"> • Complete all pre-start and running checks before any activity takes place • The shutdown procedures must only be completed by the candidate at the end of the test • All additional test requirements can be completed in any order
Operator safety and observations	Seat belt must be worn if stated in the employer's risk assessment / method statement. The telescopic handler must be serviceable and accessories i.e. (hoses, fittings, attachments) must be compatible, meets the current legislation
Test	The learner must: <ul style="list-style-type: none"> • Prepare truck for travel and travel to location of load A • Travel up and down a gradient • Travel over rough, uneven terrain • Pass through a chicane/restriction forward and reverse direction • Pick up load A and travel route again • Whilst travelling up the incline, stop and start truck • Place load A onto loading out tower. Then move away • Retrieve load A and lower to ground level • Travel with load A in reverse in a straight line for minimum 20 metres • Place load A at a given point • Place 3 x load B onto vehicle bed • Retrieve 3 x load B from vehicle bed • Stack 3 x load B on top of one another • De-stack 3 x load B and place alongside each other • Pick up load C and place at ground level by means of full horizontal reach • Demonstrate undercutting both lifting and placing • Travel to park position, shut down and secure
Specifications	Loads: Load A – 1 x load not less than 50% of trucks rated capacity Load B - 3 x equal dimensions suitable for stacking Load C - 1 x load of a weight less than trucks lift capacity at full horizontal reach Lorry bed: Equipped with headboard. (may be simulated must be of same dimensions including bed / ground height) Loading out tower: 75% or more of trucks maximum lift height and able to safely support load A Area / Terrain: Level ground Rough, uneven terrain Slope(s) not less than 18% (1:5.5) incline with enough manoeuvring area at both bottom and top A straight run of at least 20metres

Dimensions & Notes	<p>ACTIVITY GUIDELINES CONT'D</p> <p>Chicane clearance must not be more than 300mm or 10% of the machines width (whichever is the greater) between the truck and chicane sides, when carrying out each turn. Chicane may be adjusted to compensate for load width</p> <p>When travelling incline with load A, stop and restart truck without any unintentional movement backwards</p> <p>Stacking 3 x Load B on top of one another must be at least 15 metres away from vehicle bed</p> <p>De – stacking 3 x Load B, place alongside each other with no more than 75mm clearance</p> <p>Undercutting may be carried out with any of the lifting manoeuvres</p> <p>When using a 360° Telescopic Handler, the slewing mechanism may be used to perform duties in The Learner must section providing they are within manufacturers guidelines for the particular machine in use</p>
Test timings:	The test must be completed within 2hrs.
Shutdown procedures	Park the truck in appropriate area and carry out shut down and securing procedures